

# Project No. 15: WyEast Road - Centralvale to Sylvester

**Estimated Project Cost: \$645,975**

**Project Priority: High**

## Project Description

A total of 2,700ft of 10-in diameter waterline will be installed along WyEast Road, beginning at Centralvale Drive and ending at Sylvester Drive, replacing existing 4-in waterline. The upsized waterline will improve fire flows and distribution capacity to the west side of Odell and reduce high flow velocities through this section. The upsized line will also serve as a portion of the primary supply line to the new West Side Reservoir.

