

CIP 24: Neal Creek Road and Thomsen Road Water Line Replacement

Project Cost: \$3,100,000

Project Priority: Medium

Project Description

Beginning on Neal Creek Road, approximately 9,800 ft of 8-in water line will be installed, upsizing existing 4-in lines and providing a new route for water to flow on Thomsen Road. The waterline will end on Thomsen Road approximately 2,000 ft south of Fir Mountain Road, will install a new pipe in an area with known leaks, and will improve fire flows, distribution capacity, and redundancy within the Odell Pressure Zone.

